



Key	
	PV Array
	Security Fence
	Access Route
	Overhead Electrical Cables
	PRoW
	Hedgerow
	Site Boundary
	Hardstanding Area
	DNO Substation
	Customer Substation

CONSTRUCTION ISSUE

<p>JA Solar, JAM72S30 535/MR Solar Modules @ 15° Pitch, Ground Mount System - TBC Spacing - back to front = 4.50m front to front = 11.12m Inverters (Huawei) 185KTL = 81 Transformers 3000KVA = 4 Transformers 2500KVA = 1 Transformers 1000KVA = 1</p> <p>No. of 535W modules = 34992 modules</p> <p>Total Installed Capacity = 18.72 MWp</p> <p>Declared Net Capacity = 14.99 MW</p>
--

Installer Details
Anesco Ltd.
The Green,
Easter Park,
Benyon Road,
Reading,
RG7 2PQ
Tel: 0845 894 4444

Comments
Site area - 67.76acres 27.42h/a
Grid Reference: SY 32789 98192
Ordnance Survey, (c) Crown Copyright 2020. All rights reserved.
Licence number 100022432

Revision	Description	Revised By	Approved By	Date
A	Issued for comment	JH		15/01/2021
B	RLB altered	MS		29/03/2021

Scale	Drawn By	Checked By	Signed by PM	Date Checked	Page	Sheet
1:4000 @ A3	JH				1 of 1	A3

Installation Address
BEAVOR GRANGE FARM, SECTOR
LANE STAMMERY
HILL, DEVON, EX13
5SE

Project	BEAVOR GRANGE FARM
Title	SITE LAYOUT - OPTION 1
Drawing No.	Q20 0171_03

