

Key	
	Site Boundary
	Security Fence
	Access Track
	Public Rising Main
	Overhead Electrical Cables
	Ethylene Pipeline
	High Pressure Gas Pipeline
	LV Cable Route
	Utilities Easement
	DNO Substation
	Customer Substation
	LV Substation
	Hardstanding Area
	PV Array - JA Solar, 540W Modules

**NOT FOR CONSTRUCTION ISSUE**

540W JA Solar Modules @ 15° Pitch  
 Ground Mount System - TBC  
 Spacing - back to front = 4.50m  
 front to front = 11.12m  
 Inverters - Huawei 185KTL = 213


Total no. of modules = 92016 modules  
 Transformers 3000KVA = 13  
 Transformers 1500KVA = 01

Total Installed Capacity = 49.688MWp

Declared Net Capacity = 39.405MW

Installer Details  
 Anesco Ltd.  
 The Green,  
 Easter Park,  
 Benyon Road,  
 Reading,  
 RG7 2PQ  
 Tel: 0845 894 4444

Comments  
 Area - 164.65acres/ 66.63Ha  
 Length of Fence - 4049.25m



Revision	Description	Revised By	Approved By	Date
A	Renamed and numbered from Carlism Hill Q20_0074_03	JH		22/07/2021
B	TIC & DNC amended	JH		27/07/2021
C	Redrawn onto topological survey plan, TIC & DNC amended	PJB		25/08/2021

Scale	Drawn By	Checked By	Signed by PM	Date Checked	Page	Sheet
1:4000@A2	JH				1 of 1	A2

Installation Address  
 Land at Turf Carr,  
 Bransholme,  
 Hull,  
 HU11 5EF

Project	TURF CARR
Title	SITE LAYOUT
Drawing No.	C0002455_02
Rev.	B

